

**Bid Addendum Notice**  
**Bagmati Rural Municipality**  
**Office of Rural Municipal Executive,**  
**Bhattedanda, Lalitpur**

Invitation for Bids No.: BAGL/NCB/WORKS/079/080-05

Date of publication: 26-12-2022

1. Changes are made in the Bill of Quantities (BOQ) part of the document of contract for the works Gaupalika Stariya Rangasala Nirman (BAGL/NCB/WORKS/079/080-05). The following is the revised BOQ.



# **Bid Addendum Report**

## **Bagmati Rural Municipality**

Bagmati Rural Municipality  
Bhattedada  
Lalitpur  
Bagmati Province  
Bagmati Gaupalika  
Nepal

**Addendum No: 1**

**Published On: 26-12-2022 00:00**

**Invitation No: BAGL/NCB/WORKS/079/080-05**

**Dated On: 18-12-2022 00:00**

# Chapter: Bill of Quantities

1 Provisional Sum					
Procurement Item Details					
SL. No	Item Description	Unit	Quantity	Unit Rate(in NPR)	Amount(in NPR)
1	Insurance of works, plants, materials, loss and damage to equipments, Contractor's workmen and employees and third party insurance against damage to other persons and property	PS	1	100000	100000
2	Carry out additional tests for material and works as required and instructed by the Project Manager.	PS	1	50000	50000
3	Provide and installation of project information board of size 1.80 m X 1.2 m along with iron posts including excavation, concreting, backfilling etc all complete as per DoR Standard Specification for Road and Bridge Works.(DoR SS 110)	PS	1	10000	10000

2 Construction work						
Procurement Item Details						
SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
1	Earthwork in excavation from Hydraulic Excavator in medium type soils in foundation including m hauling distance and 1.8 m, lift all complete in approval of site engineer.	cum	327.07			
2	Supplying and Soling of stone in proper line and level all complete as per approved drawing, Specification and instruction of site engineer.	cum	40.31			
3	Plain cement Concrete (PCC) in 1:2:4 ratio for foundations and flooring with approved quality of cement, sand and machine crushed stone aggregate including supply of materials, mixing, laying curing the work at least 7 days etc all complete as per approved drawing, Specification and instruction of site engineer.	cum	20.15			
4	Plain cement Concrete (PCC) for RCC works M 20 (1:1.5:3) for slab/lintels/columns/beams with approved quality of cement, sand and machine crushed stone aggregate including supply of materials, mixing, laying, curing the work at least 7 days etc all complete as per approved drawing, Specification and instruction of site engineer.	cum	92.74			

*[Handwritten Signature]*

*[Handwritten Signature]*


## Procurement Item Details

SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
5	TMT steel reinforcement bar of fe 500 grade, including supplying, straightening, cleaning, cutting, binding & fixing in position with annealed tying binding wire all complete as per approved drawing, Specification and instruction of site engineer.	kg	12560.18			
6	Formwork, shuttering, centering with 19 mm thick waterproof ply board and steel post for all works necessary propping, scaffolding, staging, supporting inclusive of wedging and cutting holes for utilization till the support is fully unyielding nett all complete as per approved drawing, S [pecification and instruction of site engineer.	sqm	792.38			
7	Good quality local chimney made Brickwork in 1:4 C/S mortar up to Ground floor in perfect line level finish including supply of materials, wetting the bricks, racking the joints and curing the for at least 7 days all complete as per approved drawing, Specification and instruction of site engineer.	cum	22.09			
8	Stone masonry works in 1:6 C/S mortar up to Ground floor in perfect line level finish including supply of materials, wetting the bricks, racking the joints and curing the work for at least 7 days all complete as per approved drawing, Specification and instruction of site engineer.	cum	67.24			
9	Supply and Laying of 12.5 mm thick cement sand plaster in (1:4) ratio on wall of good finish including supply of materials, racking the joint, wetting of surfaces & curing the work at least 7 days all complete as per approved drawing, Specification and instruction of site engineer.	sqm	423.74			
10	Earth filling in 150 mm thick layer, watering, ramming including supply of filling materials within 10 m diatance all complete as per approved drawing, Specification and instruction of site engineer.	cum	65.41			

*[Handwritten signature]*

## Procurement Item Details

SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
11	Supplying and fitting of Steel Structure for Railing as per approved drawing, Specification and instruction of site engineer.	kg	5741.73			
12	Supplying and applying Enamel Paint of approved Colour on Iron Railing Surface all complete works as per Specification and instruction of site engineer.	sqm	576.33			
13	Site clearance work before and after construction of Building.	sqm	6378.46			
14	Earthwork in excavation in medium type soils in foundation from 0.8 cum Capacity Hydraulic Excavator all complete in approval of site engineer.	cum	7491.11			
15	Gravel filling including supply of filling materials, watering, ramming etc. all complete as per approved drawing, Specification and instruction of site engineer.	cum	39.08			
16	Plain cement Concrete (PCC) in 1:2:4 ratio for foundations and flooring with approved quality of cement, sand and machine crushed stone aggregate including supply of materials, mixing, laying curing the work at least 7 days etc all complete as per approved drawing, Specification and instruction of site engineer.	cum	98.56			
17	Plain cement Concrete (PCC) for RCC works M 20 (1:1.5:3) for slab/lintels/columns/beams with approved quality of cement, sand and machine crushed stone aggregate including supply of materials, mixing, laying, curing the work at least 7 days etc all complete as per approved drawing, Specification and instruction of site engineer.	cum	98.56			
18	Tor steel reinforcement bar of fe 500 grade, including supplying, straightening, cleaning, cutting, binding & fixing in position with annealed tying binding wire all complete as per approved drawing, Specification and instruction of site engineer.	MT	11.6			




## Procurement Item Details

SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
19	Stone masonry works in 1:6 C/S mortar up to Ground floor in perfect line level finish including supply of materials, wetting the bricks, racking the joints and curing the work for at least 7 days all complete as per approved drawing, Specification and instruction of site engineer.	cum	195.0			
20	Formwork, shuttering, centering with 19 mm thick waterproof ply board and steel post for all works necessary propping, scaffolding, staging, supporting inclusive of wedging and cutting holes for utilization till the support is fully unyielding nett all complete as per approved drawing, Specification and instruction of site engineer.	sqm	659.96			